

FWP0001646

CANYONLEIGH BAUXITE PIT FORWARD PROGRAM

Thursday 15 May 2025 to Sunday 14 May 2028

Summary

DETAIL	
Mine	Canyonleigh Bauxite Pit
Reference	FWP0001646
Forward program commencement date	Thursday 15 May 2025
Forward program end date	Sunday 14 May 2028
Forward program revision (if applicable)	
Contact	Sinead Kelly
Mining leases	PLL 1236 (1924)
Project location	Pgh Bricks & Pavers Pty Limited
Date of submission	Friday 11 July 2025

Important

The department may make the information in your program and any supporting information available for inspection by members of the public, including by publication on its website or by displaying the information at any of its offices. If you consider any part of your program to be confidential, please communicate this to the department via the message function on this submission within the NSW Resources Regulator Portal.

Three-year forecast – surface disturbance activities

Project description

The Canyonleigh site is on Lot 1 DP 516824, located off Canyonleigh Road within the Wingecarribee Shire Local Government Area. The site is located approximately 17km southwest of Moss Vale. Access to the Canyonleigh site is off Canyonleigh Road to the north of the site. PLL1236 was granted May 15th 1969 to extract Group 2 and group 5 minerals (Bauxite and Clay) and is valid until May 15 2040.

Description of surface disturbance activities

Exploration activities

No exploration is expected to occur within the next 3 years.

Construction activities

No construction activities are expected to occur on site within the next 3 years.

Mining schedule

Mining development method and sequencing and general mine features.

No new disturbance is forecast for the Forward Program period. Mining sequence and staging for the next 3 years is in accordance with the rehabilitation management plan. When mining recommences, extraction will occur in the west and south-western corner of the site on areas that are disturbed. The existing batter slopes of 1 horizontal: 1.5 vertical for the Bauxite will be continued.

Areas identified for emplacements, the sequencing of emplacements, construction, and management.

There will be very little overburden generated within the next three years as mining continues within the existing disturbed active mining area. Overburden, if encountered will be placed within the existing overburden emplacement areas in the eastern portion of the active void and the perimeter of the void.

Processing infrastructure activities and the location of tailings facilities and schedule for emplacement.

There are no tailings on this site.

Waste disposal and materials handling operations.

Putrescible waste, such as non-recyclables from the office and workshop will be collected by Council waste pickups. Hydrocarbons from potential fuel spills will be contained and collected using spill kits and will be taken to an appropriately licenced landfill and documented. Any contaminated soils will be assessed and will be treated as directed by appropriately qualified specialists.

Key production milestones

MATERIAL	UNIT	YEAR 1	YEAR 2	YEAR 3
Stripped topsoil (if applicable)	(m ³)	1,500	1,500	1,500
Rock/overburden	(m ³)	4,000	4,000	4,000
Ore	(Mt)	0.01	0.01	0.01
Reject material¹	(Mt)	0	0	0
Product	(Mt)	0	0	0

¹ This includes coarse rejects, tailings and any other wastes resulting from beneficiation.

Three-year rehabilitation forecast

Rehabilitation planning schedule

Rehabilitation planning schedule

Monitoring of rehabilitation areas will continue over the forward program period. Weed management and possible reseeding of the western face may occur depending on mining campaign duration. During this time, suggestions and feedback received from the resources regulator will be considered in future rehabilitation operations and plans.

Stakeholder consultation

No stakeholder consultation is expected to occur over the next 3 years.

Rehabilitation studies, risk assessments and/or design work

No rehabilitation studies, risk assessments or design work is expected to be conducted over the next three years.

Rehabilitation research and trials

RRT NUMBER	PROJECT/TRIAL NAME	OBJECTIVE OF TRIAL/PROJECT	METHODOLOGY	EXPECTED DATE OF COMPLETION	STATUS
---------------	--------------------	----------------------------	-------------	--------------------------------	--------

FWP0001
646

Rehabilitation maintenance and corrective actions

Rehabilitation maintenance and corrective action procedures are outlined in the rehabilitation management plan. Monitoring of rehabilitation areas will continue over the forward program period. During this time, suggestions and feedback received from the resources regulator will be considered in future rehabilitation operations and plans. There are no areas identified on the site that require corrective actions during the reporting period.

Rehabilitation schedule

As outlined in the previous Forward Program, a rehabilitation strip has been prepared during the previous mining campaign in the eastern portion of the pit. Vegetation matter and topsoil has been placed over this and will be monitored over the next three years. No other rehabilitation is planned for the next three years though if this changes the areas will be added to an amended forward program.

Completion of rehabilitation

No areas of rehabilitation are completed or expected to be completed in the next three years.

Subsidence remediation for underground operations

No subsidence monitoring or remediation works are proposed to be conducted over the next three years.

Progressive mining and rehabilitation statistics

Three-yearly forecast cumulative disturbance and rehabilitation progression

	FORECAST	UNIT	YEAR 1	YEAR 2	YEAR 3
A1	Total disturbance footprint - surface disturbance	(ha)	4.4	4.4	4.4
B	Total active disturbance	(ha)	4.02	4.02	4.02
P	Total new area of land proposed for active rehabilitation	(ha)	0	0	0

Rehabilitation key performance indicators (KPIs)

	FORECAST	UNIT	YEAR 1	YEAR 2	YEAR 3
O	Total new disturbance area during reporting period	(ha)			
P	Total new area of land proposed for rehabilitation during the reporting period	(ha)			
Q	Annual rehabilitation to disturbance ratio				

Attachment 1 – Reporting Definitions

REPORTING CATEGORY	DEFINITION
A Total disturbance footprint – surface disturbance	All areas within a mining lease that either have at some point in time or continue to pose a rehabilitation liability due to surface disturbance activities. The total disturbance footprint is the sum of the total active disturbance, decommissioning, landform establishment, growth medium development, ecosystem and land use establishment, ecosystem and land use development and rehabilitation completion (see definitions below). Underground mining operations should not include the footprint of underground mining areas/subsidence management areas in the total disturbance footprint.
B Total active disturbance	Includes on-lease exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste rock emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped) and temporary stabilised areas (e.g. areas sown with temporary cover crops for dust mitigation and temporary rehabilitation).
C Rehabilitation – land preparation	Includes the sum of all disturbed land within a mining lease that have commenced any, or all, of the following phases of rehabilitation – decommissioning, landform establishment and growth medium development. Refer to the glossary of terms in this document for the definition of these phases of rehabilitation.
D Ecosystem and land use establishment	Includes the area which has been seeded/planted with the target vegetation species for the intended final land use. However, vegetation has not matured to a stage where it can be demonstrated that it will be sustainable for the long term and or require only a maintenance regime consistent with target reference/analogue sites. Typically, rehabilitation areas would be in this phase for at least two years (and usually more) before rehabilitation can be classified as being in the ecosystem and land use development phase. This phase does not apply to infrastructure areas that are being retained as part of final land use for the site.

REPORTING CATEGORY	DEFINITION
O	The area of any new active disturbance that will be created during the next three years, as defined under definition A1 (definition A1 Table 5).
P	The sum of any new rehabilitation to be commenced in the next three years. These areas may be in the phases “Rehabilitation - Land Preparation” or the “Ecosystem & Land Use Establishment” (definitions C & D in Table 5).
Q	The rehabilitation to disturbance ratio (S / R) indicates how many hectares of new rehabilitation are undertaken for each hectare of land disturbed during the three years. A ratio of 1/1 indicates that the area of new rehabilitation and disturbance in that period are the same.

Attachment 2 – Definitions

WORD	DEFINITION
Active	In the context of rehabilitation, land associated with mining domains is considered ‘active’ for the period following disturbance until the commencement of rehabilitation.
Active mining phase of rehabilitation	In the context of rehabilitation, the active mining phase of rehabilitation constitutes the rehabilitation activities undertaken during mining operations such as salvaging and managing soil resources, salvaging habitat resources, and native seed collection. This phase also includes management actions taken during operations to manage risks to rehabilitation and enhance rehabilitation outcomes such as selective handling of waste rock and management of tailings emplacements.
Analogue site	In the context of rehabilitation, an analogue site is a ‘reference site’ that represents an example of the defining characteristics (such as vegetation composition and structure or agricultural productivity) of the final land use. Characteristics of analogue sites can be assessed to develop the rehabilitation objectives and completion criteria for final land use domains.
Annual rehabilitation report and forward program	As described in the Mining Regulation 2016.
Annual reporting period	As defined in the Mining Regulation 2016.
Closure	A whole-of-mine-life process, which typically culminates in the relinquishment of the mining lease. It includes decommissioning and rehabilitation to achieve the approved final land use(s).
Decommissioning	The process of removing mining infrastructure and removing contaminants and hazardous materials.
Decommissioning Phase of Rehabilitation	Activities associated with the removal of mining infrastructure and removal and/or remediation of contaminants and hazardous materials. In the context of the rehabilitation management plan this phase of rehabilitation may also include studies and assessments associated with decommissioning and demolition of infrastructure or works carried out to make safe or ‘fit for purpose’ built infrastructure to be retained for future use(s) following lease relinquishment.

WORD	DEFINITION
Department	The Department of Regional NSW.
Disturbance	See Surface Disturbance.
Disturbance area	An area that has been disturbed and that requires rehabilitation. This may include areas such as on-licence exploration areas, stripped areas ahead of mining, infrastructure areas, water management infrastructure, sewage treatment facilities, topsoil stockpile areas, access tracks and haul roads, active mining areas, waste emplacements (active/unshaped/in or out-of-pit), tailings dams (active/unshaped/uncapped), and areas requiring rehabilitation that are temporarily stabilised (i.e. managed to minimise dust generation and/or erosion).
Domain	An area (or areas) of the land that has been disturbed by mining and has a specific operational use (mining domain) or specific final land use (final land use domain). Land within a domain typically has similar geochemical and/or geophysical characteristics and therefore requires specific rehabilitation activities to achieve the associated final land use.
Ecosystem and Land Use Development	This phase of rehabilitation consists of the activities to manage maturing rehabilitation areas on a trajectory to achieving the approved rehabilitation objectives and completion criteria. For vegetated land uses this phase may include processes to develop characteristics of functional self-sustaining ecosystems, such as nutrient recycling, vegetation flowering and reproduction, and increasing habitat complexity, and development of a productive, self-sustaining soil profile. This phase of rehabilitation may include specific vegetation management strategies and maintenance such as tree thinning, supplementary plantings and weed management.
Ecosystem and Land Use Establishment	This phase of rehabilitation consists of the processes to establish the approved final land use following construction of the final landform. For vegetated land uses this rehabilitation phase includes establishing the desired vegetation community and implementing land management activities such as weed control. This phase of rehabilitation may also include habitat augmentation such as installation of nest boxes.
Exploration	Has the same meaning as that term under the State Environmental Planning Policy (Mining, Petroleum Production and Extractive Industries) 2007.

WORD	DEFINITION
Final landform and rehabilitation plan	As defined in the Mining Regulation 2016.
Final land use	As defined in the Mining Regulation 2016.
Form and way	Means the form and way approved by the Secretary. Approved form and way documents are available on the Department's website.
Growth Medium Development	This phase of rehabilitation consists of activities required to establish the physical, chemical and biological components of the substrate required to establish the desired vegetation community (including short lived pioneer species). This phase may include spreading the prepared landform with topsoil and/or subsoil and/or soil substitutes, applying soil ameliorants to enhance the physical, chemical and biological characteristics of the growth media, and actions to minimise loss of growth media due to erosion.
Habitat	Has the same meaning as that term under the <i>Biodiversity Conservation Act 2016</i> and the <i>Fisheries Management Act 1994</i> (as relevant).
Indicator	An attribute of the biophysical environment (e.g. pH, topsoil depth, biomass) that can be used to approximate the progression of a biophysical process. It can be measured and audited to demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion criterion (i.e. defined end point). It may be aligned to an established protocol and used to evaluate changes in a system.
Land	As defined in the <i>Mining Act 1992</i> .
Landform Establishment	This phase of rehabilitation consists of the processes and activities required to construct the final landform. In addition to profiling the surface of rehabilitation areas to the approved final landform profile this phase may include works to construct surface water drainage features, encapsulate problematic materials such as tailings, and prepare a substrate with the desired physical and chemical characteristics (e.g. rock raking or ameliorating sodic materials).
Large mine	As defined in the Mining Regulation 2016.
Lease holder	The holder of a mining lease.

WORD	DEFINITION
Life of mine	The timeframe of how long a mine is approved to mine, from commencement to closure.
Mine rehabilitation portal	Means the NSW Resources Regulator’s online portal that lease holders must use (via a registered account) to: ■ upload rehabilitation geographical information system (GIS) spatial data ■ develop rehabilitation GIS spatial data (using online tracing functions) ■ generate rehabilitation plans and rehabilitation statistics using the map viewer and Rehabilitation Key Performance Indicator functionalities. Data submitted to the mine rehabilitation portal is collated in a centralised geodatabase for use by the NSW Resources Regulator to regulate rehabilitation performance of lease holders.
Mining area	As defined in the <i>Mining Act 1992</i> .
Mining domain	A land management unit with a discrete operational function (e.g. overburden emplacement), and therefore similar geophysical characteristics, that will require specific rehabilitation treatments to achieve the final land use(s).
Mining land	As defined in the <i>Mining Act 1992</i> .
Native vegetation	Has the same meaning as that term under section 60B of the <i>Local Land Services Act 2013</i> .
Overburden	Material overlying coal or a mineral deposit.
Performance indicator	An attribute of the biophysical environment (for example pH, slope, topsoil depth, biomass) that can be used to demonstrate achievement of a rehabilitation objective. It can be measured and audited to demonstrate (and track) the progress of an aspect of rehabilitation towards a desired completion criterion, that is, a defined end point. It may be aligned to an established protocol and used to evaluate changes in a system.

WORD	DEFINITION
Phases of rehabilitation	The stages and sequences of actions required to rehabilitate disturbed land to achieve the final land use. The phases of rehabilitation are: ■ active mining ■ decommissioning ■ landform Establishment ■ growth medium development ■ ecosystem and land use establishment ■ ecosystem and land use development.
Progressive rehabilitation	The progress of rehabilitation towards achieving the approved rehabilitation completion criteria. This may be described in terms of domains, phases, performance indicators and rehabilitation completion criteria.
Rehabilitation Completion	The final phase of rehabilitation when a rehabilitation area has achieved the approved rehabilitation objectives and rehabilitation completion criteria for the final land use. Rehabilitation areas may be classified as complete when the NSW Resources Regulator has determined in writing that the relevant rehabilitation obligations have been fulfilled following submission of <i>Form ESF2 Rehabilitation completion and/or review of rehabilitation cost estimate</i> application by the lease holder.
Rehabilitation Completion criteria	As defined in the Mining Regulation 2016.
Rehabilitation cost estimate	As defined in the Mining Regulation 2016.
Rehabilitation management plan	As defined in the Mining Regulation 2016.
Rehabilitation objectives	As defined in the Mining Regulation 2016.
Rehabilitation risk assessment	As defined in the Mining Regulation 2016.
Rehabilitation schedule	The defined timeframes for progressive rehabilitation set out in the forward program.

WORD	DEFINITION
Relevant stakeholders	Means any persons or bodies who may be affected by the mining operations, including rehabilitation, carried out on the lease land, and includes: ■ the relevant development consent authority ■ the local council ■ the relevant landholder(s) ■ community consultative committee (if required under the development consent) or equivalent consultative group ■ affected land holder(s) ■ government agencies relevant to the final land use ■ affected infrastructure authorities (electricity, telecommunications, water, pipeline, road, rail authorities) ■ local Aboriginal communities, and ■ any other person or body determined by the Minister to be a relevant stakeholder in relation to a mining lease.
Risk	The effect of uncertainty on objectives. It is measured in terms of consequences and likelihood (AS/NZS ISO 31000:2009).
Secretary	The Secretary of the Department.
Security deposit	An amount that a mining lease holder is required to provide and maintain under a mining lease condition, to secure funding for the fulfilment of obligations under the lease (including obligations that may arise in the future).
Surface disturbance	Includes activities that disturb the surface of the mining area, including mining operations, ancillary mining activities and exploration.
Tailings	A combination of the fine-grained solid material remaining after the recoverable metals and minerals have been extracted from the mined ore, and any process water ² .
Waste	Has the same meaning as that term under the <i>Protection of the Environment Operations Act 1997</i> .

² Commonwealth of Australia (DITR), 2007. *Tailings Management*.

Attachment 3 – Plans

2A 2025-07-08.pdf

2B 2025-07-08.pdf

2C 2025-07-08.pdf

Forward Program (LARGE MINE) v2.5

Canyonleigh Bauxite Pit Plan 2A FWP0001646 15 May 2025 - 14 May 2028



Legend

Forecast Data Year1

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Forecast Data Year2

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Forecast Data Year3

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Project Approval Boundary

World Imagery

Low Resolution 15m Imagery

High Resolution 60cm Imagery

High Resolution 30cm Imagery

Citations



1: 2,673



135.8 0 67.89 135.8 Meters

WGS_1984_Web_Mercator_Auxiliary_Sphere
© DRE

This map is a user generated static output from an Internet mapping site and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.

THIS MAP IS NOT TO BE USED FOR NAVIGATION

Notes

Plan Date 08/07/2025

Submission IDs:

8189, 10433

Nil new disturbance or rehabilitation areas proposed from 2025 - 2028.

Canyonleigh Bauxite Pit Plan 2B FWP0001646 15 May 2025 - 14 May 2028



Legend

Forecast Data Year1

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Forecast Data Year2

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Forecast Data Year3

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Project Approval Boundary

World Imagery

Low Resolution 15m Imagery

High Resolution 60cm Imagery

High Resolution 30cm Imagery

Citations



1: 2,673



135.8 0 67.89 135.8 Meters

WGS_1984_Web_Mercator_Auxiliary_Sphere
© DRE

This map is a user generated static output from an Internet mapping site and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.

THIS MAP IS NOT TO BE USED FOR NAVIGATION

Notes

Plan Date 08/07/2025

Submission IDs:

8189, 10429

Nil new disturbance or rehabilitation areas proposed from 2025 - 2028.

Canyonleigh Bauxite Pit Plan 2C FWP0001646 15 May 2025 - 14 May 2028



Legend

Forecast Data Year1

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Forecast Data Year2

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Forecast Data Year3

- Forecast Disturbance
- Forecast Land Prepared for Rehabi
- Ecosystem and Land Use Establish

Project Approval Boundary

World Imagery

Low Resolution 15m Imagery

High Resolution 60cm Imagery

High Resolution 30cm Imagery

Citations



1: 2,673



135.8 0 67.89 135.8 Meters

WGS_1984_Web_Mercator_Auxiliary_Sphere
© DRE

This map is a user generated static output from an Internet mapping site and is for reference only. Data layers that appear on this map may or may not be accurate, current, or otherwise reliable.

THIS MAP IS NOT TO BE USED FOR NAVIGATION

Notes

Plan Date 08/07/2025

Submission IDs:

8189, 10430

Nil new disturbance or rehabilitation areas proposed from 2025 - 2028.



Open Cut Summary Rehabilitation Cost Estimation

Note: Sections of this page are automatically filled in from the registration page

Mine Name:	Canyonleigh Clay Mine		
Lease(s):	PLL1236		
Authorisation Owner:	PGH Bricks and Pavers Pty Ltd		
Term of RCE:	End of FWP 14 May 2028		
Current Security:	\$133,000	Date of Last Security Deposit Review:	11/07/2024
Mine Contact:	Joe Gauci, 0417 683 526, jgauci@csr.com.au		

Domain		Security Deposit
Domain 1: Infrastructure		\$10,096
Domain 2: Tailings & Rejects		
Domain 3: Overburden & Waste		\$7,993
Domain 4: Active Mine & Voids		\$39,431
Domain 5: Management Activities		\$28,210
Subtotal (Domains and Sundry Items)		\$85,731
Contingency	10%	\$8,573
Post Closure Environmental Monitoring	10%	\$8,573
Project Management and Surveying	10%	\$8,573
Total Security Deposit for the Mining Project (excl. of GST)		\$111,450

Note: GST is not included in the above calculation or as part of rehabilitation security deposits required by the Department.

- ☐ Alterations have been made to unit prices within this spreadsheet. (Attach a separate sheet providing details of changes).
- ☒ The proposed rehabilitation design is generally consistent with the development consent for the project.

This mine security calculation has been estimated using the best available information at the time.
It is a true and accurate reflection of the total rehabilitation liability held by this mine.

Joe Gauci
Company Representative's Name

11/07/2025
Date

National Raw Materials Manager
Company Representative's Role / Responsibility


Signature